



NORTH LONDON AD FACILITY, HERTFORDSHIRE

Size of site:	3.7 hectares
Input:	Up to 85KT of solid and liquid packaged and unpackaged food waste
Digesters:	4No. 4,200m ³
Storage:	4,200m ³
Power Output:	3MWe
Commissioned:	DECEMBER 2016
Construction period	12 months



CIVIL WORKS

Completed in 6 months



5.5m deep reinforced concrete basement
with underground tanks



100m³ underground reinforced
concrete leachate tank

1500m² silage clamp with RC retaining walls

7500m² of running areas



For more information, please contact John Haigh on 0207 305 5325